## **AW-HE40 Firmware Update Procedure**

#### Please be sure to read this first.

The update of AW-HE40 camera is performed via a network from Web setting screen on PC. There might be accidents in the process of updating such as changing the camera settings and others by mistake. Please perform the update after taking every situation into careful consideration.

It is recommended that the current settings should be noted down in advance.

◆ [ Disclaimer of warranty ]

IN NO EVENT SHALL Panasonic Corporation BE LIABLE TO ANY PARTY OR ANY PERSON, EXCEPT FOR REPLACEMENT OR

REASONABLE MAINTENANCE OF THE PRODUCT, FOR THE CASES, INCLUDING BUT NOT LIMITED TO BELOW.

(1) ANY DAMAGE AND LOSS, INCLUDING WITHOUT LIMITATION, DIRECT OR INDIRECT, SPECIAL, CONSEQUENTIAL OR EXEMPLARY, ARISING OUT OF OR RELATING TO THE PRODUCT.

(2) PERSONAL INJURY OR ANY DAMAGE CAUSED BY INAPPROPRIATE USE OR NEGLIGENT OPERATION OF THE USER.

(3) UNAUTHORIZED DISASSEMBLE, REPAIR OR MODIFICATION OF THE PRODUCT BY THE USER.

(4) INCONVENIENCE OR ANY LOSS ARISING WHEN IMAGES ARE NOT DISPLAYED, DUE TO ANY REASON OR CAUSE INCLUDING ANY FAILURE OR PROBLEM OF THE PRODUCT.

(5) ANY PROBLEM, CONSEQUENTIAL INCONVENIENCE, OR LOSS OR DAMAGE, ARISING OUT OF THE SYSTEM COMBINED BY THE DEVICES OF THIRD PARTY.

(6) ANY INCONVENIENCE, DAMAGES OR LOSSES RESULTING FROM ACCIDENTS CAUSED BY AN INADEQUATE INSTALLATION METHOD OR ANY FACTORS OTHER THAN A DEFECT IN THE PRODUCT ITSELF.

(7) LOSS OF REGISTERED DATA CAUSED BY ANY FAILURE.

(8) ANY DAMAGE OR CLAIMS DUE TO LOSS OR LEAKAGE OF IMAGE DATA OR SETTING DATA SAVED ON THIS UNIT OR ON A MEMORY CARD OR COMPUTER.

◆[ Network security ]

As connected to a network, your attention is called to the following security risks.

(1) Leakage or disclosure of information transmitted via this unit

(2) Unauthorized use of this unit by a third person with malicious intent

(3) Interference or stoppage of this unit by a third person with malicious intent

It is your responsibility to take sufficient network security measures such as those described below to protect yourself against the above risks.

+ Use this unit in a network secured by a firewall, etc.

+ If this unit is used in a system with a computer connected, make sure that checks for and removal of computer viruses and malicious programs are implemented regularly.

+ Do not install the unit in a location where the unit, cables, and other parts may be easily damaged.

### Preparing the update file

1. Download the latest software to the hard disk of your PC from web site.

https://eww.pass.panasonic.co.jp/pro-av/support/content/download/EN/ep2main/soft/he40\_note\_e.htm

2. Copy the file "\*\*\*\*\*.zip" to hard disk of your PC and extract the file.

The folder contains the following three software programs for upgrading. [Note]

Spaces and double-byte characters cannot be used for saving directory.

Please do not change unzipped folder's name and files inside it.

### <Connection AW-HE40 to PC >

AW-HE40	LAN cable		ſ	
<when hub="" is<="" th=""><th>used &gt;</th><th></th><th></th><th></th></when>	used >			
AW-HE40	LAN straight cable	HUB	LAN straight cable	

The LAN straight cable is used when making the connection through a switching hub.

Select an IP address for the personal computer within the private address range while ensuring that it is different from the address of the unit. Set the subnet mask to the same address as the unit.

Example

AW-HE40	192. 168. 0. 10
PC	192. 168. 0. 100

Unit's IP address a	nd subnet mask (factory settings)
IP address	: 192.168.0.10
Subnet mask	: 255.255.255.0
Range of private	e addresses: 192.168.0.1 to 192.168.0.254

### **Firmware Version**

The version of firmware can be confirmed on the WEB setting screen.

[WEB Browser] Product info. screen (Setup  $\rightarrow$  Maintenance  $\rightarrow$  Product info.)

Live Setup	System log Product info. State	us Default reset Backup Activate
Setup menu	Model no.	AW-UE70
Basic	MAC address	20-C6-EB-EF-40-0E
Basic	Serial no.	F5TBA0015
Image/Audio	Firmware version	Ver.1.01
Multi-screen	Activation counter	0
User mng.	Operation time	28h
Network	OSS license display	View
Maintenance	Firmware file E:\UPDATE.HDC	參照
Power	It will take around 10 min Please wait and do not ope	utes to complete the update . erate the browser during this process .
Power ON Standby		

You can also check the version in the camera menu.

[ Camera menu ]	Maintenance $\rightarrow$ Firmware Version	
-----------------	--	--

## Maintenance ##	### Firmware Version ###
⇔ Firmware Version IP Network Initialize	Ver.1.0
Return	⇔Return

# Update procedure using WEB browser

1. Turn on the Camera after connecting a PC via the local network.



2. Start the WEB browser, and access following URL.

For example: http://192.168.0.10

3. The following WEB setting screen is displayed. Click Setup button.

Live Setup		
Multi-screen		
Single -		
Compression		
H.264 JPEG		
Stream		
1 2 3 4		
Other Menu >>		
Power		
Power ON Standby		
	Zoom D-Ext. Brightness Preset	
	Focus Auto Scene	
	Near O.T. AF Far Speed Slow F.Auto Set	

4. Click the OK button on the next screen.





The first time you use the setup menu, a login screen will appear. Enter the following initial values\* and click "OK".

User name	admin
Password	12345

\*The Username and Password if you have changed them.

- 5. In the setup menu select: Maintenance > Product info.
- 6. Click the Browse button and select the update file "UPDATE.HDC" on the selection screen.

Setup menu       Model no.       AW-UE70         Basic       MAC address       20-C6-EB-EF-40-0E         Serial no.       F5TBA0015         Firmware version       Ver.1.01	Live Setup	System log Product info. Status Default reset Backup Activate
Basic     F5TBA0015	Setup menu	Model no. AW-UE70
Serial no. F5TBA0015		MAC address 20-C6-EB-EF-40-0E
Image/Audio         Firmware version         Ver.1.01	Basic	Serial no. F5TBA0015
	Image/Audio	Firmware version Ver.1.01
Multi-screen Activation counter 0	Multi-screen	Activation counter 0
User mng. Operation time 28h	User mng.	Operation time 28h
Network OSS license display View	Network	OSS license display
Firmware file E:\UPDATE.HDC Execute 8	Maintenance	E:\UPDATE.HDC
Power It will take around 10 minutes to complete the update . Please wait and do not operate the browser during this process .	Power	It will take around 10 minutes to complete the update . Please wait and do not operate the browser during this process .
Power ON Standby	Power ON Standby	

- If you have successfully selected the update file, you will be told how long the update will take.
   If you select a file other than "UPDATE.HDC", you will be shown an error "Invalid firmware file..."
   Please select the correct file.
- 8. Press the Execute button to display the update confirmation screen.

Microso	ft Internet Explorer 🛛 🛛 🔀
?	When the [OK] button is clicked , start update . Proceed ?
	OK Cancel

9. When you click the OK button on the confirmation screen, the message "Sending firmware file..." is displayed. The firmware file is transferred from the PC to the camera.

\*"[ERROR] Invalid firmware file. Select again." is displayed, select the correct file again.

Live Setup	System log Product info. Status E	Default reset Backup Activate
Setup menu	Model no.	AW-UE70
Basic	MAC address	20-C6-EB-EF-40-0E
Basic	Serial no.	F5TBA0015
Image/Audio	Firmware version	Ver.1.01
Multi-screen	Activation counter	0
User mng.	Operation time	28h
Network	OSS license display	View
Maintenance	Firmware file C:\Temp\UPDATE.HDC	参照
Power	Sending firmware file (00:11)	
Power ON Standby		

10. Once the firmware is transferred to the camera, the update begin and progress is displayed.

User mng.	Now Updating (04:36)
	· * * * * * * * * * * * * * * * * * * *
Network	It will take <b>around 10 minutes</b> to complete the update . Please wait and do not turn off the power during this process . Please do not operate the browser during the update process .
Maintenance	



During the update, the camera's LED lamp blinks green.

The update will take approx.10 minutes. Do not disconnect the power

while updating. During the update, the power of the camera will automatically restart. Do not close the web setting screen or accidentally turn off the power.

11. When the update is completed, the following completion message will be displayed. Click the OK button to display the live screen of the web setting screen.



The update is now complete.

Please make sure your version is updated.

#### ■NDI|HX Upgrade

If you have already purchased the NDI|HX Upgrade from the NewTek store, please refer back to the email and PDF instructions on how to upgrade NDI|HX for your device.

If you have not already purchased the NDI|HX Upgrade from the NewTek store, please visit: <u>http://new.tk/ndi\_panasonic</u> https://store.newtek.com/index.php/panasonicndihxlicense-1.html

About NDI: NewTek NDI (Network Digital Interface) allows you to connect video equipment across a network. Your production switcher, capture system, media server—any NDI-enabled device on the network—can see and access content from all other devices, allowing more sources than ever before to be used for live production. NDI|HX is a high efficiency mode which enables cameras to have built-in support for NDI technology all over a single Ethernet cable.

# **Update procedure using Windows tools**

The camera can also be updated using Windows apps tools such as EasyIPSetupTool and Integrated Camera Update Tool.

Please refer to the previous pages for the initial settings. In addition, if you are using a Mac, update using a web browser.

## ■ EasyIPSetupToolPlus

Supported OS Windows 10 Windows 11

1. Download the application file from the following web site.

https://eww.pass.panasonic.co.jp/pro-av/support/content/download/EN/ep2main/easyIPplus\_e.htm


 Extract the downloaded zip file, double-click [EasyIPSetupToolPlus.exe] in the folder [DV91000536\*] to start "EasyIPSetupToolPlus".

### **Update procedure**

A list of cameras on the network is displayed. You can confirm the camera version here.

1. [Firmware Update]

												÷		×
	All Net	twork												
		IPv4 Address	Model	Title	Category	Version	Status	DHCP	Port	Mac Address	Serial Number	Admini	strator Registri	ation
		192.168.0.12	UE4	AW-UE4	САМ	01.57	Power ON	OFF	80	4C-36-4E-64-00-DC	Unsupported	Done		
		192.168.0.11	UE4	AW-UE4	САМ	01.57	Power ON	OFF	80	4C-36-4E-63-FB-9C		Done		
		192.168.0.15	GA-ASW8T···		Other					00-50-40-35-81-36				
• • •		192.168.0.10	UE100	AW-UE100	CAM	01.10	Standby	OFF	80	A8-13-74-C6-0B-2F	H0TBA0042	Done		
Lamp Settings Web Gut		Q 👤 arch AutoIP	Administrator Registration	1 Firmware Update										



#### **2.** [Auto]

If your PC is connected to the internet, the application will identify PTZ cameras that need to be upgraded. In addition, all operations from the download of the firmware file to the version upgrade of the PTZ camera are performed by applications.

[Manual]

You can update using the firmware file downloaded and prepared in advance.

- **3.** Mark the left column of the displayed camera IP address list and select the camera you want to update.
- 4. [User ID: Password: ]

Enter the ID and PW set as the initial account. And push the Input button.

- 5. [Firmware File: ]In manual mode, specify the downloaded firmware file. And push the Input button.
- **6.** [Update] Push the button to start the update.

Firmware update takes approx.10 min.


Do not power down or disconnect the LAN cable between the PC and Camera while updating.

- **7.** An update completion message will be displayed.
- **8.** The update is completed by the above procedure. Please make sure your version is updated.

Please refer to the EasyIPSetupToolPlus Operation Manual for details.

### The update was not completed

If you disconnected the LAN cable or the power supply during the update, please try again. [<!>Update is failed]



- Please reconfirm the network settings, circumstances, ID and password.

- If [Power ON] or [Standby] is selected too quickly, the status selected and the display shown may not correspond. In a case like this, press the [F5] key on the keyboard of the PC to restore the correct status display.

## ■ Integrated Camera Update Tool

- This tool is the software for updating firmware of Integrated Cameras.
- If this software is installed into PC and then the camera that needs updating is connected via network with this PC, the camera can be updated simply by loading the update files.
- If you are using a Mac, you cannot use this tool, so please update using a web browser.

Supported OS
Windows7
Windows8.1
Windows10

Download the update tool from "Download" from the following web site for AW-HE40. https://eww.pass.panasonic.co.jp/pro-av/support/content/download/EN/ep2main/soft/he40\_note\_e.htm

•Before executing, make sure of the remote camera's IP address using Easy IP Setup Software, etc. •Also, turn on the remote camera. While executing, do not turn off the remote camera.

•Depending on the PC and network environment in use, it may take approximately 5 - 30 minutes. •When "OK" on the "Success" or "Fail" screen is clicked, the instruction to reboot will be issued to the remote camera.

#### **Update Procedure**

 Starting up Integrated Camera Update Tool Do not start up other web browsers when this tool is used. Also, do not open two or more operation screens of this tool at the same time.

🧶 Integrated Camera U	Ipdate Tool
IP Address Camera Info Ve	192 . 168 . 0 . 10 Ddel: Connect Ddel: 3
Select Firmware File ID Password	admin 5
	Execute

- Entering IP address and acquiring information of remote camera Enter the remote camera's IP address in the (1) and click "Connect" (2). If the communication is correctly done with the remote camera, its model number and current version number will be displayed at the (3).
- Selecting firmware and entering ID & Password Click "Browse" (4) to select the firmware file to be updated. Then enter ID & Password as necessary (5).

4. Execution

When "Execute" (6) is clicked, the firmware will start to be transferred from PC to the remote camera.

And, after this transfer is completed, the remote camera will automatically update its own firmware.

While transferring or updating, the progress bar (7) will work.

5. When the firmware update is completed, "Success" screen will be shown. When you push "OK" button, the remote camera will reboot automatically.



#### **Errors**

If it is NOT completed, "Fail" screen will be shown.

Message	×
8	Fail Update.
	ОК

When you push "OK" button, the remote camera will reboot automatically. Execute update again.